






Indicative list of works which may or may not require consent under S.23 of the Land Drainage Act 1991

	Pipe Culvert (including extension and removal of) Consent Required under Section 23 1(b).
	Oversized Box Culvert (including extension and removal of) Consent Required under Section 23 1(b).
	Trash Screens - Consent Required as it is an alteration to a culvert and has the potential to obstruct flow
	Bank Protection Works - Not Consentable under LDA 91, (Temporary works may require consent).
	Pipe Crossing (in channel) - Consent Required under Section 23 1(a)
	Pipe Crossing (above bank) - Not Consentable under LDA 91 as it does not interfere with flow.
	Pipe Crossing (below bed) - Not Consentable under LDA 91 as it does not interfere with flow – Potential temporary works consent.
	Protruding Pipe Outfall - Not Consentable under LDA 91 as it will not act like a dam/weir or like obstruction.
	Outfall within Bank profile - Not Consentable under LDA 91 as it does not interfere with flow – Potential temporary works consent.
	Weir/Dam or impoundment or temporary works that obstruct flow - Consent Required under Section 23 1(a)
	Bridge (where soffit level is below bank top level) - Consent Required under Section 23 1(a) if it has the potential to affect flow.
	Bridge (abutments protruding but not reducing flow area/width) - Not Consentable under LDA 91 as does not interfere with flow.
	Bridge (Abutments restricting flow) or Flume - Consent Required under Section 23 1(b)
	Clear span bridge - Not Consentable as it does not interfere with flow